



Camp Old Indian Utility Improvements

This project included a Preliminary Engineering Report, field survey, design, bidding and construction administration for improvements to the potable water storage and distribution network for 22 campsites including new bath-houses and the installation of a wastewater collection system, master pump station and master septic tank system with remote leach field.

Scope:

- The potable water portion of the project consisted of upgrades to two (2) existing 12,000 gallon above-ground water storage tanks, upgrade to the existing booster pump and installation of approximately 11,845 linear feet of new HDPE waterline, including related appurtenances and campsite connections.
- The wastewater portion of the project consisted of 10,000 feet of low pressure HDPE forcemain piping from the campsites, a master wastewater pump station, 2,500 linear feet of 4-inch DIP forcemain and a master septic field with 10,698 feet of double stone drain line.

The Project Entire Project
Preliminary Engineering Report
Preliminary Design
Field Location Survey
Final Design
Construction Services

Contract Value: \$922,600

Contract Period:

Principal Contractor:



WASTEWATER



DESIGN SOUTH
PROFESSIONALS, INC.
engineers architects planners