



# Orr Street Regional Detention Pond City of Anderson

This project included preliminary design, design, bidding, and construction services for three stormwater detention ponds in series to replace a deteriorated 72-inch piping system along an unnamed branch of Rocky River.

- A parallel overflow piping system was included to attenuate peak flows within a limited area
- The project consists of approximately 700 feet of 48-inch and 60-inch overflow piping, triple-run 60-inch outfall system, concrete overflow structures, connections to existing piping systems to remain, clearing and grading, erosion control, and site stabilization.

➤ Project videos and photo slideshows can be found at [www.youtube.com/StormwaterCOA](http://www.youtube.com/StormwaterCOA)

The Project: Entire Project  
Preliminary Engineering Report  
Preliminary Design  
Field Location Survey  
Final Design  
Construction Services

Contract Value: \$497,048

Contract Period:

Principal Contractor: Richards Construction

STORMWATER



**DESIGN SOUTH**  
**PROFESSIONALS, INC.**

engineers architects planners